

SCHEDULE OF PRICES  
(BREAKDOWN BY STREET)  
2020 STREET UTILITY CONSTRUCTION  
CITY OF FOND DU LAC

ADDENDUM #1  
REVISED 02/13/2020

Pay Item	Item Description	11th	HAZOTTE-DIVISION	FIREHOUSE LOT 1	FOLLETT	MILITARY	DIVISION ELEC	Total	UNIT
100-06	6" SDR 35 PVC Sanitary Sewer Laterals	1319	408	0	124	2167	0	4017	LNFT
100-08	8" SDR 35 PVC Sanitary Sewer Main	2101	908	0	0	1461	0	4470	LNFT
100-10	10" SDR 35 PVC Sanitary Sewer Main	149	26	0	0	898	0	1073	LNFT
100-24	24" PS46 PVC Sanitary Sewer Main	0	0	0	404	0	0	404	LNFT
110-04	4 Ft Dia Standard Precast Sanitary Sewer Manhole Including: Frame & Cover, Complete in Place	5	2	0	0	12	0	19	EACH
111-04	4 Ft Dia Standard Precast Sanitary Sewer Manhole With Flat Top Including: Frame & Cover, Complete in Place	0	2	0	0	0	0	2	EACH
112-04	4 Ft Dia Standard Precast Sanitary Sewer Outside Drop Manhole Including: Frame & Cover, Complete in Place	1	0	0	0	1	0	2	EACH
120-01	Core and Connect to Existing Sanitary Sewer Manhole (8" Pipe)	2	0	0	0	0	0	2	EACH
120-03	Core and Connect to Existing Sanitary Sewer Manhole (12" Pipe)	0	0	0	0	1	0	1	EACH
120-10	Core and Connect to Existing Sanitary Sewer Manhole (8" Pipe) Including Bench Modification	0	0	0	0	1	0	1	EACH
120-21	Connect to Existing Sanitary Sewer Main	0	1	0	1	3	0	5	EACH
120-95	Connect to Existing Sanitary Sewer Lateral	21	0	0	0	0	0	21	EACH
121-01	Seal Existing Sanitary Sewer Main	0	0	0	0	1	0	1	EACH
121-02	Abandon Existing Sanitary Sewer Manhole	0	2	0	0	11	0	13	EACH
123-24	24" Sanitary Sewer Bulkhead	0	0	0	1	0	0	1	EACH
124-04	2" Polystyrene Insulation - Sanitary Sewer	0	1037	0	0	0	0	1037	SQFT
200-24	24" Storm Sewer Pipe	194	0	0	0	0	0	194	LNFT
200-30	30" Storm Sewer Pipe	592	0	0	0	0	0	592	LNFT
200-36	36" Storm Sewer Pipe	49	0	0	0	0	0	49	LNFT
201-12	12" Class III Reinforced Concrete Storm Sewer	586	0	0	0	495	0	1081	LNFT
201-15	15" Class III Reinforced Concrete Storm Sewer	331	234	0	0	784	0	1349	LNFT
201-18	18" Class III Reinforced Concrete Storm Sewer	0	0	0	0	653	0	653	LNFT
201-24	24" Class III Reinforced Concrete Storm Sewer	83	0	0	0	0	0	83	LNFT
201-30	30" Class III Reinforced Concrete Storm Sewer	0	0	0	0	309	0	309	LNFT
201-36	36" Class III Reinforced Concrete Storm Sewer	0	0	0	0	216	0	216	LNFT
201-42	42" Class III Reinforced Concrete Storm Sewer	0	0	0	4	0	0	4	LNFT
204-06	6" SDR 35 PVC Storm Sewer Laterals	1333	362	0	95	343	0	2133	LNFT
204-08	8" SDR 35 PVC Storm Sewer Main	0	68	0	0	107	0	175	LNFT
204-10	10" SDR 35 PVC Storm Sewer Main	0	0	140	0	0	0	140	LNFT
204-12	12" SDR 35 PVC Storm Sewer Main	0	23	142	0	0	0	165	LNFT
204-15	15" SDR 35 PVC Storm Sewer Main	0	455	50	0	0	0	505	LNFT
208-12	12" Class V Reinforced Concrete Storm Sewer	0	260	0	67	0	0	327	LNFT
215-04	4 Ft Dia Standard Precast Storm Sewer Manhole Including: Frame & Cover, Complete in Place	0	2	0	0	0	0	2	EACH
216-04	4 Ft Dia Standard Precast Storm Sewer Manhole With Flat Top Including: Frame & Cover, Complete in Place	2	2	0	0	11	0	15	EACH
216-06	6 Ft Dia Standard Precast Storm Sewer Manhole With Flat Top Including: Frame & Cover, Complete in Place	6	0	0	0	1	0	7	EACH
216-08	8 Ft Dia Standard Precast Storm Sewer Manhole With Flat Top Including: Frame & Cover, Complete in Place	0	0	0	0	1	0	1	EACH
216-24	4 Ft Dia Standard Precast Storm Sewer Manhole With Flat Top Including: Type "H" Catch Basin Frame (R-3067) &	0	3	0	0	0	0	3	EACH
216-95	6 Ft Dia Doghouse Precast Storm Sewer Manhole With Flat Top Including: Frame & Cover, Complete in Place	0	0	0	1	0	0	1	EACH
216-96	6 Ft Dia (OG) Standard Precast Storm Sewer Manhole With Flat Top Including: 2050 Frame & Cover, Complete in	0	0	0	0	1	0	1	EACH
217-01	Type "H" Catch Basin Including: Frame (R-3067) & Grate (Type-R), Complete in Place	7	5	0	4	8	0	24	EACH
217-02	Type "H" Catch Basin Including: Frame (R-3067) & Grate (Type-L), Complete in Place	4	0	0	0	11	0	15	EACH
218-24	24" Dia Field Inlet Including: Frame (R-5901-E) & Grate (Type-G), Complete in Place	0	0	1	0	1	0	2	EACH
218-36	36" Dia Field Inlet Including: Frame (R-5901-H) & Grate (Type-G), Complete in Place	0	0	4	0	0	0	4	EACH
220-06	6 Ft Dia Precast Storm Sewer Manhole with 4 Ft Sump Including: Frame & Cover, Complete in Place	0	1	0	0	0	0	1	EACH
220-08	8 Ft Dia Precast Storm Sewer Manhole with 4 Ft Sump Including: Frame & Cover, Complete in Place	1	0	0	0	1	0	2	EACH
230-01	Connect to Existing Storm Sewer Structure (Existing Opening)	2	1	0	0	0	0	3	EACH
230-02	Connect to Existing Storm Sewer Structure (New Connection)	0	0	1	0	0	0	1	EACH
230-04	Connect to Existing Storm Sewer Main	3	0	0	0	1	0	4	EACH
230-05	Connect to Existing Storm Lateral	0	2	1	0	9	0	12	EACH
231-01	Abandon and Seal Existing Catch Basin	10	5	0	0	7	0	22	EACH
231-02	Abandon Existing Storm Manhole	2	0	0	0	1	0	3	EACH
231-03	Seal Existing Storm Sewer Main	1	0	0	0	0	0	1	EACH
231-05	Abandoned Storm Sewer Fill (Cellular Concrete or Sand)	3	0	0	0	10	0	12	CUYD
231-06	Remove Existing Storm Sewer 30" and Smaller	0	0	0	0	212	0	212	LNFT

SCHEDULE OF PRICES  
(BREAKDOWN BY STREET)  
2020 STREET UTILITY CONSTRUCTION  
CITY OF FOND DU LAC

ADDENDUM #1  
REVISED 02/13/2020

Pay Item	Item Description	11th	HAZOTTE-DIVISION	FIREHOUSE LOT 1	FOLLETT	MILITARY	DIVISION ELEC	Total	UNIT
231-07	Remove Existing Storm Sewer 33" and Larger	0	0	0	0	38	0	38	LNFT
312-02	Inlet Protection - Type B	0	0	3	0	0	0	3	EACH
312-04	Inlet Protection - Type D	15	8	6	6	26	14	75	EACH
312-06	Inlet Protection - Type D-M	11	8	0	4	20	0	43	EACH
400-04	4" PVC DR18 Water Main	0	0	0	0	43	0	43	LNFT
400-06	6" PVC DR18 Water Main	403	558	0	8	108	0	1076	LNFT
400-08	8" PVC DR18 Water Main	1424	480	0	401	209	0	2514	LNFT
400-10	10" PVC DR18 Water Main	0	0	0	0	73	0	73	LNFT
400-12	12" PVC DR18 Water Main	0	0	0	0	2138	0	2138	LNFT
401-06	6" Ductile Iron Water Main Including Nitrile Gaskets	0	0	0	0	16	0	16	LNFT
401-08	8" Ductile Iron Water Main Including Nitrile Gaskets	0	0	0	0	56	0	56	LNFT
401-12	12" Ductile Iron Water Main Including Nitrile Gaskets	0	0	0	0	200	0	200	LNFT
406-04	Connect to Existing 4" Water Main	0	0	0	0	1	0	1	EACH
406-06	Connect to Existing 6" Water Main	3	0	0	1	2	0	6	EACH
406-08	Connect to Existing 8" Water Main	1	2	0	1	2	0	6	EACH
406-10	Connect to Existing 10" Water Main	0	0	0	0	1	0	1	EACH
407-01	32# Anode Bag	4	1	0	1	3	0	9	EACH
407-02	Temporary 2" Blow Off	2	0	0	1	1	0	4	EACH
407-04	2" Polystyrene Insulation - Water Main and Services	52	0	0	32	14	0	99	SQFT
410-04	4" Water Main Valve and Box	0	0	0	0	1	0	1	EACH
410-06	6" Water Main Valve and Box	8	2	0	0	7	0	17	EACH
410-08	8" Water Main Valve and Box	2	2	0	1	2	0	7	EACH
410-10	10" Water Main Valve and Box	0	0	0	0	1	0	1	EACH
410-12	12" Water Main Valve and Box	0	0	0	0	4	0	4	EACH
413-03	6"x 6" Tee	2	0	0	0	0	0	2	EACH
413-05	8"x 6" Tee	7	2	0	1	0	0	10	EACH
413-06	8"x 8" Tee	2	1	0	0	1	0	4	EACH
413-08	10"x 6" Tee	0	0	0	0	1	0	1	EACH
413-10	10"x 10" Tee	0	0	0	0	1	0	1	EACH
413-11	12"x 4" Tee	0	0	0	0	1	0	1	EACH
413-12	12"x 6" Tee	0	0	0	0	5	0	5	EACH
413-13	12"x 8" Tee	0	0	0	0	2	0	2	EACH
413-14	12"x 10" Tee	0	0	0	0	1	0	1	EACH
414-06	6"-90° Bend	3	0	0	1	1	0	5	EACH
414-08	8"-90° Bend	1	1	0	0	1	0	3	EACH
414-10	10"-90° Bend	0	0	0	0	1	0	1	EACH
415-06	6"-45° Bend	1	3	0	0	0	0	4	EACH
415-08	8"-45° Bend	4	0	0	0	1	0	5	EACH
416-04	4"-22½° Bend	0	0	0	0	2	0	2	EACH
416-06	6"-22½° Bend	8	3	0	0	2	0	13	EACH
416-08	8"-22½° Bend	0	0	0	2	0	0	2	EACH
416-12	12"-22½° Bend	0	0	0	0	4	0	4	EACH
419-06	6" Cap on Existing Main	5	1	0	2	1	0	9	EACH
419-08	8" Cap on Existing Main	0	1	0	0	1	0	2	EACH
419-10	10" Cap on Existing Main	0	0	0	0	2	0	2	EACH
420-06	6" Plug	2	0	0	0	0	0	2	EACH
420-08	8" Plug	3	2	0	2	1	0	8	EACH
420-10	10" Plug	0	0	0	0	1	0	1	EACH
420-12	12" Plug	0	0	0	0	1	0	1	EACH
430-04	1¼" Water Service Including: Corp, Stop, Box Saddle and Union	46	12	0	10	21	0	89	EACH
430-05	1¼" Polyethylene Water Service Pipe	1383	289	0	317	712	0	2701	LNFT
430-07	1½" Water Service Including: Corp, Stop, Box Saddle and Union	0	3	0	0	0	0	3	EACH
430-08	1½" Polyethylene Water Service Pipe	0	49	0	0	0	0	49	LNFT
430-95	1" Copper Service Pipe	0	0	0	0	100	0	100	LNFT

SCHEDULE OF PRICES  
(BREAKDOWN BY STREET)  
2020 STREET UTILITY CONSTRUCTION  
CITY OF FOND DU LAC

ADDENDUM #1  
REVISED 02/13/2020

Pay Item	Item Description	11th	HAZOTTE-DIVISION	FIREHOUSE LOT 1	FOLLETT	MILITARY	DIVISION ELEC	Total	UNIT
440-01	Fire Hydrant	3	2	0	0	5	0	10	EACH
440-02	Abandon Existing Hydrant	3	1	0	0	5	0	9	EACH
500-02	Cobra Head Street Light Concrete Base, Pole, Arm and Luminaire Installation	0	0	0	0	0	3	3	EACH
500-03	Cobra Head Street Light Concrete Base, Pole, Arm and Luminaire	0	0	0	0	10	0	10	EACH
500-08	Ornamental Street Light Pole and Luminaire	11	8	0	4	0	5	28	EACH
500-20	Remove Concrete Bases	0	0	0	0	0	9	9	EACH
500-98	Move Existing Light Pole & Base, (Pour New Base)	0	0	1	0	0	0	1	EACH
500-99	Parking Lot Light: New Concrete Base- Pole, Arm and Luminaire Remove and Reinstallation	0	0	5	0	0	0	5	EACH
501-01	Conduit, PVC, 1" Diameter	0	141	0	0	44	0	185	LNFT
501-02	Conduit, PVC, 1" Diameter, Schedule 80	0	0	335	0	0	0	335	LNFT
501-07	Conduit, PVC, 2" Diameter	3125	1393	0	408	4397	0	9323	LNFT
501-08	Conduit, PVC, 2" Diameter, Schedule 80	451	142	0	36	254	0	883	LNFT
501-09	Directional Boring Including: 2" Diameter PVC Conduit	0	0	0	0	0	1325	1325	LNFT
501-98	Directional Boring Including: 2" Diameter PVC Conduit Schedule 80	0	0	0	0	0	186	186	LNFT
502-01	Electrical Wire 6 AWG	7901	3049	0	1308	5636	4532	22426	LNFT
502-03	Electrical Wire Tracer 12 AWG	643	518	0	36	2725	0	3922	LNFT
502-04	Cable Type UF 2-12 AWG	0	160	0	80	400	220	860	LNFT
502-05	Electrical Wire 8 AWG	2634	1016	0	436	1879	1511	7475	LNFT
502-06	Electrical Wire #10 THHN/THWN (Hot Conductors)	0	0	967	0	0	0	967	LNFT
502-07	Electrical Wire #10 THHN/THWN (Equipment Grounding Conductors)	0	0	484	0	0	0	484	LNFT
502-20	Loop Detector Lead In Cable	0	9	0	0	0	0	9	LNFT
502-21	Loop Detector Wire	0	39	0	0	0	0	39	LNFT
503-01	Electrical Access Box, Plastic	21	7	0	5	18	5	56	EACH
503-03	Electrical Access Box, Polymer Concrete	4	1	0	0	0	0	5	EACH
503-10	12"x48" Steel Pull Box	0	4	0	0	2	0	6	EACH
504-02	Electrical Service Meter Pedestal	1	0	0	0	1	1	3	EACH
504-95	Salvage & Repair Loop Detector	0	2	0	0	0	0	2	EACH
600-01	Traffic Control & Mobilization	0	0	0	0	1	0	1	LPSM
600-03	Portable Changeable Message Boards	0	14	0	0	28	0	42	DAY
601-01	Sidewalk & Driveway Removal	445	111	0	42	719	23	1342	SQYD
601-02	4" Concrete Sidewalk and Carriage Walk	3954	2941	362	399	18287	208	26151	SQFT
601-06	6" Concrete Drive Approach & Sidewalk	5053	2785	416	1331	9214	0	18799	SQFT
601-11	Concrete Steps	0	0	0	0	22	0	22	SQFT
601-23	6" Wide Variable Height Concrete Pedestrian Curb	0	0	0	0	52	0	52	LNFT
601-24	Drilled Sidewalk Bars (#4x12")	190	40	0	34	99	0	363	EACH
601-26	4" Diameter x 18" PVC Sign Sleeve	0	3	3	0	0	0	6	EACH
601-29	Detectable Warning Field	0	0	30	0	13	0	43	SQFT
601-30	24"x60" Detectable Warning Field	15	2	0	0	7	0	24	EACH
602-01	Sawcut Asphalt Pavement	2724	0	0	56	70	0	2850	LNFT
602-02	Sawcut Concrete Pavement	0	83	0	10	536	0	629	LNFT
603-20	30" Concrete Curb & Gutter - Standard	2781	1949	0	0	4270	0	8999	LNFT
603-27	36" Concrete Curb & Gutter - Standard	210	47	0	0	157	0	415	LNFT
603-31	24" Concrete Curb & Gutter - Standard	0	0	0	0	20	0	20	LNFT
603-33	Remove & Replace 30" Concrete Curb & Gutter	0	0	297	0	0	0	297	LNFT
603-50	Drilled Tie Bars (#6x 12")	0	0	0	0	37	0	37	EACH
603-52	Drilled Dowel Bars (1½"x 18")	0	26	0	0	28	0	54	EACH
603-54	Drilled Tie Bars (#4x 12")	0	4	0	8	26	0	38	EACH
603-61	Concrete Pavement Gaps	0	0	0	0	6	0	6	EACH
603-95	18" Concrete Curb and Gutter	0	0	0	0	42	0	42	LNFT
603-97	12" Concrete Curb	0	0	166	0	0	0	166	LNFT
603-98	Sawcut and Remove Existing Curb Head	0	0	31	0	0	0	31	LNFT
604-01	3" Asphalt Driveway and Trail	0	14	0	0	478	0	492	SQYD
604-02	6" Gravel Driveway	0	0	0	0	43	0	43	SQYD
605-06	Common Excavation	2366	1777	1210	795	10800	0	16948	CUYD

SCHEDULE OF PRICES  
**(BREAKDOWN BY STREET)**  
 2020 STREET UTILITY CONSTRUCTION  
 CITY OF FOND DU LAC

ADDENDUM #1  
 REVISED 02/13/2020

Pay Item	Item Description	11th	HAZOTTE-DIVISION	FIREHOUSE LOT 1	FOLLETT	MILITARY	DIVISION ELEC	Total	UNIT
605-07	6" Deep Excavation Below Subgrade & Crushed Aggregate Base Course Backfill - 3" Dense Base (Areas to be Dete	1277	987	610	400	2478	0	5753	SQYD
605-13	Break Pavement	0	0	0	0	9456	0	9456	SQYD
606-01	4" Topsoil, Seed, Fertilizer, & Hydromulch	3257	578	100	621	5306	0	9862	SQYD
606-06	Restoration Watering	55	10	0	10	89	0	164	TGAL
606-96	Remove and Replace Landscaping	0	6	0	0	126	0	131	SQYD
606-97	Miscellaneous Restoration Firehouse (Screening)	0	0	1	0	0	0	1	LPSM
606-99	1-yr Landscaping Warranty	0	0	1	0	0	0	1	LPSM
607-04	Remove and Replace Pavers	0	39	0	0	21	0	60	SQFT
607-05	Relocate Mailbox: Including Remove, Temporarily Relocate and Permanently Replace	0	0	0	0	7	0	7	EACH
608-01	Common Excavation (Asphalt Alt)	645	790	0	217	0	0	1652	CUYD
608-12	6" Crushed Aggregate Base Course - 1¼" Dense Base (Asphalt Alt)	0	0	0	0	10415	0	10415	SQYD
608-14	8" Crushed Aggregate Base Course - 1¼" Dense Base (Asphalt Alt)	6436	3949	2435	1601	881	0	15303	SQYD
608-18	6" Crushed Aggregate Base Course - 3" Dense Base (Asphalt Alt)	5933	3949	2435	1601	711	0	14629	SQYD
608-22	Crushed Aggregate Base Course - 3" Dense Base (Asphalt Alt)	0	0	0	0	10415	0	10415	CUYD
608-32	2½" Asphalt Binder Course (Asphalt Alt)	6084	4846	2325	1279	1280	0	15815	SQYD
608-42	2" Asphalt Surface Course (Asphalt Alt)	6084	3024	2325	1279	1280	0	13992	SQYD
608-97	8½" Concrete Pavement (Asphalt Alt)	0	139	0	0	7996	0	8135	SQYD
609-12	6" Crushed Aggregate Base Course - 1¼" Dense Base (Concrete Alt)	5109	3949	0	1601	10415	0	21074	SQYD
609-14	8" Crushed Aggregate Base Course - 1¼" Dense Base (Concrete Alt)	1292	0	2435	0	881	0	4608	SQYD
609-18	6" Crushed Aggregate Base Course - 3" Dense Base (Concrete Alt)	788	0	2435	0	711	0	3934	SQYD
609-22	Crushed Aggregate Base Course - 3" Dense Base (Concrete Alt)	0	0	0	0	10415	0	10415	CUYD
609-32	2½" Asphalt Binder Course (Concrete Alt)	1299	0	2325	0	1280	0	4904	SQYD
609-42	2" Asphalt Surface Course (Concrete Alt)	1299	0	2325	0	1280	0	4904	SQYD
609-97	8½" Concrete Pavement (Concrete Alt)	4786	3164	0	1279	7996	0	17225	SQYD
801-01	Pavement Marking , Epoxy, 4"	0	0	0	0	4835	0	4835	LNFT
801-02	Pavement Marking , Epoxy, 6"	0	0	0	0	137	0	137	LNFT
801-03	Pavement Marking , Epoxy, 8"	0	0	0	0	352	0	352	LNFT
801-11	Pavement Marking , Epoxy, 24" Diagonal	0	0	0	0	78	0	78	LNFT
801-99	Pavement Marking & Signs	0	0	1	0	0	0	1	LPSM
802-01	Pavement Marking, Epoxy, Arrows, Type 1	0	0	0	0	4	0	4	EACH
802-02	Pavement Marking, Epoxy, Arrows, Type 2	0	0	0	0	7	0	7	EACH
802-04	Pavement Marking, Epoxy, Arrows, Type 3	0	0	0	0	2	0	2	EACH
803-02	Pavement Marking, Epoxy, Words	0	0	0	0	2	0	2	EACH
803-04	Pavement Marking, Epoxy, Stopline , 18-Inch	0	0	0	0	29	0	29	LNFT
803-11	Pavement Marking, Epoxy, Bike Lane Arrows	0	0	0	0	16	0	16	EACH
803-12	Pavement Marking, Epoxy, Bike Lane Symbols	0	0	0	0	15	0	15	EACH