City of Fond du Lac
Bike Pedestrian Plan--Recommended Projects

ID #	Map Ref.	Street	From	To	Project Category[1]	Plan Section[2]	Project Description	Sign Changes	Policy Changes	Urgency/ Oppor-tunity[4]
IV.a.i).1		Martin Ave.	Prairie Trail	new st.	B	L	Add pavement markings over RR overpass			L/P
IV.a.i).2		Martin Ave.	Prairie Trail	bridge	M	L	Add trail under bridge, up abutments to cloverleaf into bridge walk			L/E, L/F
IV.a.ii).1		new st.	Martin	Camelot	M	L	Survey, engineer, obtain R/W for trail along proposed E/W street			L/E, L/F
IV.a.ii).2		Camelot Dr.	new st.	Ledgeview Tr	M	L	Construct trail on E side of Camelot			L/F
IV.a.ii).3		Ledgeview Tr	Camelot (S)	Camelot (W)	M	L	Widen and pave existing trail			L/F
IV.a.ii).4		Mihill Ave.	Camelot	Pioneer	B	L	Paint sharrows on both sides of street		Consider NP?	L/P
IV.a.ii).5		Pioneer Rd.	Mihill	Main	M	L	Construct trail on S side of street			I/S
IV.a.ii).6		Park Ave.	Martin	Pioneer	B	L	Paint sharrows on both sides of street	Alternate loop		I/M
IV.a.ii).7		Pioneer Rd.	Park	Main	B	L	Encourage County to resurface Pioneer, to repaint the outside lanes and to allow sharrows.	Alternate loop		I/M, I/F
IV.a.ii).8		Camelot Dr.	new st.	Mihill	B	L	Until Ledgeview Tr. can be improved, paint sharrows on Camelot		In meantime, NP on Camelot?	L/P
IV.a.ii).9		Ledgeview Tr	Ledgeview Tr.	Ledgeview Tr	M	L	Widen and pave existing trail as it goes around the pond.	Alternate loop		L/F
IV.a.iv).1		Hickory St.	Pioneer	Dixie	B	L	Paint lanes & symbols add signage		NP to Council 9/11	I/F
IV.a.iv).2		Dixie St.	Hickory	Brooke Tr.	B	L	Paint sharrows, add signage			I/F
IV.a.v).1		Brush St.	Morris	Brooke Tr.	B	L	Paint sharrows, add signage	Alternate loop		I/M
IV.a.v).2		Oak Pl.	Western	FdL River	M	L	Improve path, Quick Freeze corner	Alternate loop		I/F
IV.a.vi).1		Brooke St.	Scott		C	L	Improve crossing at Scott & Brooke	Rect. Rapid Flashing Beacon (in-house)		I/S, I/M
IV.a.vi).2		Water St.	Scott	Spring	M	L	Create path on W side of Water	Stripe lanes for now?		L/F
IV.a.vi).3		FdL River	Spring	Promen	M	L	Create path thru Merc property or WWTP, through park toward Pavilion			L/F, LE
IV.a.vi).4		channels	Promen	Park	M	L	Improve existing paths thru 3 islands			L/F
IV.a.vi).5		Park Ave.	bridge	Harbor View	M	L	Create off-street trail on E side of Park			L/F
IV.a.vi).6		Harbor View	Mohawk		M	L	Improve NW corner crossing			I/S
IV.a.vi).7		Winnebago	DeNevue Cr	Peebles Tr	B	L	Create curb cut to allow cyclists to get onto park trails at furthest E point.	Crosswalks, inform cyclists to use road		I/S, I/F
IV.a.vi).8		Winnebago	DeNevue Cr	Peebles Tr	M	L	Construct multi-use trail N of Winnebago from creek to Peebles.			L/F
IV.a.vi).9		Spring St.	Water St.	Doty	B	L	Stripe existing pavement for bikes, and create a lane S of MSC parking lot	Alternate loop		I/M

[1] Project Category: S = sidewalk only, B = on-street bike accommodations only, M = multi-purpose trail, C = Communication (signs, markings) only.

[2] Plan Section: L = bike loop, State = Links to State trails, DOT =part of State/County project, B = local bike need, S = local sidewalk need, P = policies, C = Communication (signs, markings) only.

[3] Estimated Cost: Unless otherwise noted, cost estimates are based on in.gov survey dated March 2011.

[4] Urgency/Opportunity: **I/S** = immediate need for safety reasons, **I/F** = immediate opportunity as funding is available, **I/M** = immediate opportunity as the project is minor, **L/F** = long-term goal with funding challenges, **L/E** = long-term goal with engineering challenges, **L/P** = long-term goal as this should be tied to a larger project.

City of Fond du Lac
Bike Pedestrian Plan--Recommended Projects

ID #	Map Ref.	Street	From	To	Project Category[1]	Plan Section[2]	Project Description	Sign Changes	Policy Changes	Urgency/ Oppor-tunity[4]
IV.a.vi).10		Doty St.	Spring	Harbor View	B	L	Use sharrows to reach soccer trails	Alternate loop		I/M
IV.a.vi).11		Doty St.	Spring	Harbor View	M	L	Construct new trail thru Alliant property behind Children's Museum	Alternate loop		L/F
IV.a.vi).12		Doty St.	Sibley	Harbor View	B	L	Use sharrows & signage to connect Brooke to park if no $ for trails	Alternate loop		I/M
IV.a.vi).13		Harbor View	Main		M	L	Improve trail turn paving & signage at NE corner of Main & Harbor View	Alternate loop		I/S, I/M
IV.a.vi).14		Promen Dr.	pavilion	lighthouse	M	L	Extend lakeside trail to lighthouse	Alternate loop		L/F
IV.a.vi).15		Promen Dr.	pavilion	lighthouse	M	L	Modify existing Promen Bridge to allow bikes to cross alongside (cantilevered structure?)			L/E, L/F
IV.a.vi).16		Winnebago	Peebles Tr.	Lakeside Pk	M	L	Construct trail and bridge directly from Peebles to park trail system			L/E, L/F
IV.a.vii).1		Winnebago	Peebles Tr.	Hwy 151	B	L	Paint symbols in outside lanes, sharrows @ intersections	Alternate loop		I/M, I/S
IV.b.i).1 V.p.2.1		Pioneer Rd.	Rogersville	Scott St.	B	State	Pave shoulders, mark for bike lanes; add walk	Lanes & symbols		L/F, L/P
IV.b.i).2 V.f.1		Rolling Mea-dows Dr.	Wild Goose	Scott St.	B	State	Pave shoulders, mark for bike lanes. 23 to Scott should be off-street trail.	Lanes & symbols		L/F, L/P
IV.b.i).3		multiple	Wild Goose Tr.	Mascoutin Tr	B	State	Promote a bike route between the two trails using an established in-town route, using Hickory, Western, Seymour, Arndt, Peters, Security, Pearl, Scott, and Rolling Meadows.	Sharrows & signs		I/M
IV.b.ii).1		Johnson St.	Prairie Tr.	Hwy UU	M	State	DOT to connect Old Plank Trail to Prairie Trail (under Hwy 151) as part of Hwy 23 project.			L/F, L/E, L/P
IV.b.ii).2		Hwy 23	Hwy UU			State	DOT to construct Park & Ride at UU and 23 as part of Hwy 23 project.			L/F, L/P
IV.b.iii).1 IV.c.xii).1		Scott St.	Rolling Meadows	Water St.	B	State	If Scott St. reconstructed in the future, look to provide bike accommodation, keep walk			L/F, L/P, L/E
IV.b.iii).2		Scott St.	Pioneer	Rolling Meadows	B	State	Until new bridge project, pave shoulders on bridge approaches to make 41 crossing safer.			I/M, I/S
IV.b.iv).1		Eisenbahn Tr	Eden	Brooke St. Tr.	M	State	If future opportunity arises, look to convert railroad to multi-use trail; connect to other trails			L/F, L/P
IV.c.i).1		Pioneer Rd.	Wild Goose	Rogersville	M	DOT	Add multi-use trail beside roadway when this stretch of Pioneer Rd. reconstructed (2016?)			L/F, L/P
IV.c.ii).1		Military Rd	Hickory	Western	B	DOT	STP funds hoped to be used for this 2018 project that should include bike/ped accommodations.			L/F, L/P
IV.c.ii).2		Military Rd	Pioneer	Hickory	B	DOT	When accommodations are added N of Hickory, they should be made for this stretch, as well.			L/F, L/P

[1] Project Category: S = sidewalk only, B = on-street bike accommodations only, M = multi-purpose trail, C = Communication (signs, markings) only.

[2] Plan Section: L = bike loop, State = Links to State trails, DOT =part of State/County project, B = local bike need, S = local sidewalk need, P = policies, C = Communication (signs, markings) only.

[3] Estimated Cost: Unless otherwise noted, cost estimates are based on in.gov survey dated March 2011.

[4] Urgency/Opportunity: **I/S** = immediate need for safety reasons, **I/F** = immediate opportunity as funding is available, **I/M** = immediate opportunity as the project is minor, **L/F** = long-term goal with funding challenges, **L/E** = long-term goal with engineering challenges, **L/P** = long-term goal as this should be tied to a larger project.

City of Fond du Lac
Bike Pedestrian Plan--Recommended Projects

ID #	Map Ref.	Street	From	To	Project Category[1]	Plan Section[2]	Project Description	Sign Changes	Policy Changes	Urgency/ Oppor-tunity[4]
IV.c.iii).1		4th St.	Prairie Tr.	Country Ln	M	DOT	When the 4th/151 overpass is completed, a multi-use lane will be added.			L/F, L/P
IV.c.iii).2		4th St.	Country Ln	4th St. Way	S, B	DOT	The 4th/151 overpass should include sidewalk and bike lanes to the east side of 151.			L/F, L/P
IV.c.iv).1		Hwy V	Reinhardt Rd	Mustang Ln.	S, B	DOT	The V/151 interchange will include a Park & Ride lot, connections to the Prairie Trail, and bike/ped facilities to the south side of 151.			L/F, L/P
IV.c.iv).2 V.l.1		Hwy V	Hwy 151	N of Mustang Ln	S	DOT	When the V/151 project is done, sidewalk should be extended to the current termini N of Mustang, east side only.			L/F, L/P
IV.c.v).1		Martin Ave.	Reinhardt Rd	Park Ave	S, B	DOT	This project should include bike/ped accommodations over the new overpass.			L/F, L/P
IV.c.vi).1		Reinzi Rd	Country Ln	Hwy 151	S, B	DOT	When this connection is cut off to 151, on-street accommodations may be added to this now little-used roadway, and a parking area created.			L/F, L/P
IV.c.vi).2		Reinzi Rd	Hwy 151		M	DOT	The median in 151 should have a curb cut in the median to allow bikes to cross without lifting.			L/P
IV.c.vii).1		DuCharme Pkwy	Hwy 151		S, B	DOT	This intersection will be done in '15, bike/ped acc. should be added, median curb cut.			L/F, L/P
IV.c.viii).1		Hwy 23	Rolling Meadows	Pioneer Rd.	S, B	DOT	When the bridge on Johnson St. over Hwy 41 is reconstructed, bike/ped acc. should be added.			L/F, L/P
IV.c.ix).1		Main St.	Johnson	Merrill	B	DOT	This '18 project should include bike lanes, assuming that 4 traffic lanes are not required.			L/F, L/P
IV.c.ix).2		Main St.	Johnson	Scott	B	DOT	Consider adding bike lanes or sharrows on this stretch of Main to go from new lanes to the Park.			L/P
IV.c.ix).3 VI.h.1		Marr/Macy	Merrill	Western	B	DOT	When lanes are added north of here, consider adding 1-way bike lanes on the downtown loop			L/E, L/F, L/P
IV.c.x).1		Hwy 45	Hwy V	6th St.	S, B	DOT	This '18 project should include bike lanes and new or added sidewalk.			L/F, L/P
IV.c.x).2 V.p.5.1		Hwy 45	Hwy 151	Hwy V	S, B	DOT	As opportunities arise, paved shoulders or bike lanes should be added to this busy roadway, as well as sidewalk on the west side.			L/F, L/P
IV.c.x).3		Hwy 45	6th St.	Marr St.	B	DOT	When lanes are added to 6th St., consider adding acc. to the downtown Marr/Macy loop.			L/E, L/F, L/P
IV.c.xi).1		New Street	Hunter Ave.	Hwy 23	S, B	DOT	When a key N/S corridor is developed here, it should have bike/ped acc. to the Old Plan Trail.			L/E, L/F, L/P
IV.c.xiii).1		multiple	Scott St.	North FdL	S, B	DOT	As projects are completed on 45, Van Dyne, Peters, Pioneer or Rolling Meadows, accommodations should be brought to North FdL			L/F, L/P

[1] Project Category: S = sidewalk only, B = on-street bike accommodations only, M = multi-purpose trail, C = Communication (signs, markings) only.

[2] Plan Section: L = bike loop, State = Links to State trails, DOT =part of State/County project, B = local bike need, S = local sidewalk need, P = policies, C = Communication (signs, markings) only.

[3] Estimated Cost: Unless otherwise noted, cost estimates are based on in.gov survey dated March 2011.

[4] Urgency/Opportunity: **I/S** = immediate need for safety reasons, **I/F** = immediate opportunity as funding is available, **I/M** = immediate opportunity as the project is minor, **L/F** = long-term goal with funding challenges, L/E = long-term goal with engineering challenges, **L/P** = long-term goal as this should be tied to a larger project.

City of Fond du Lac
Bike Pedestrian Plan--Recommended Projects

ID #	Map Ref.	Street	From	To	Project Category[1]	Plan Section[2]	Project Description	Sign Changes	Policy Changes	Urgency/ Opportunity[4]
IV.d.1 VII.I.1		multiple			B	B	The in-town bike route grid should be confirmed for signage, add sharrows	Add signs and sharrows as needed		I/M
V.a.1		Pioneer Rd.	Main St.	Hwy 45	S	S	Add walk on at least one side of this busy road near schools. Safe Routes to School funding?			L/E, L/F
V.b.1		Arndt St.	Packer St.	Lincoln Av	S	S	Remove walk on N side to avoid safety conflicts, cross to S side on either side, bridge.			L/E, L/F
V.c.1		Johnson St.	National Ave	Prairie Tr.	S	S	Add walk on S side of Hwy 23 where not currently. Some homes front other street.			L/F, L/P
V.c.2		Johnson St.	Kairis Ct.	Prairie Tr.	S	S	Add walk on N side of Hwy 23 near Festival.			L/F, L/P
V.d.1		Marr & Macy	Merrill	Western	C	S	Add ped countdown at signalized intersections, include for peds walking opposite 1-way traffic.			L/F, L/P
V.e.1		Harbor View	Doty	Main	S	S	Add sidewalk on at least one side of this block under future reconstruction project.			L/F, L/P
V.f.1		Rolling Meadows	Wild Goose	Scott St.	S	S	A future reconstruction of this roadway should include a sidewalk or multi-use trail.			L/F, L/P
V.g.1		Pioneer Rd.	Grove	Security Dr.	S	S	Connect to walk on Grove, Forest, Security when Pioneer sidewalk added.			L/F, L/P
V.h.1		National Ave	Reinzi	Hwy 45	S	S	There is a 250' gap in sidewalk here that should be filled in.			I/M
V.i.1		Martin Ave.	9th St.	17th St.	S	S	There is no walk on this busy 1/2 mile stretch of Fairgrounds property (east side).			L/F, L/P
V.j.1		11th St.	Military Rd.	Hickory St.	S	S	11th has been terminated east of Military, but people still walk there. Walk should be added.			I/M
V.k.1		Country Ln	Johnson	Pine Lake	S	S	Although most walk is put in as the subdivision is developed, this area is developed but lacks walk.			I/M
V.m.1		Winnebago	Willow	Luco	S	S	Sidewalk should be added on the west side of Luco (360') and south side of Winnebago (1,200') to complete this grid.			L/E, L/F, L/P
V.n.1		Division St.	Prairie Rd.	Mariearl	S	S	S side, add walk to serve Marian sports complex.			L/F, L/P
V.o.1		Buttermilk Cr			S	S	Add a walking trail through the park.			L/F
V.p.1.1		Military Rd.	Pioneer	Rogersville	S	S	If '16 project doesn't complete entire sidewalk grid to NE, fill those gaps.			L/F, L/P
V.p.3.1		various bridge projects		41, 151	S	S	As bridges are completed over 41 on Scott, Johnson, Military & Hickory, and over 151 on Main, Martin, V, 45, and 4th, add bike/ped acc.			L/E, L/F, L/P
V.p.4.1		Hwy V	FdL	Pioneer	S	S	Sidewalk should be added on one side of this highway near a school.			L/F, L/P
VI.f.1		Meadowlands Park			S	P	Add a walking trail through the park.			L/F
VI.f.2		Hunters Grove Park			S	P	Add a walking trail through the park.			L/F

[1] Project Category: S = sidewalk only, B = on-street bike accommodations only, M = multi-purpose trail, C = Communication (signs, markings) only.

[2] Plan Section: L = bike loop, State = Links to State trails, DOT =part of State/County project, B = local bike need, S = local sidewalk need, P = policies, C = Communication (signs, markings) only.

[3] Estimated Cost: Unless otherwise noted, cost estimates are based on in.gov survey dated March 2011.

[4] Urgency/Opportunity: **I/S** = immediate need for safety reasons, **I/F** = immediate opportunity as funding is available, **I/M** = immediate opportunity as the project is minor, **L/F** = long-term goal with funding challenges, **L/E** = long-term goal with engineering challenges, **L/P** = long-term goal as this should be tied to a larger project.

City of Fond du Lac
Bike Pedestrian Plan--Recommended Projects

ID #	Map Ref.	Street	From	To	Project Category[1]	Plan Section[2]	Project Description	Sign Changes	Policy Changes	Urgency/ Oppor-tunity[4]
VI.f.3		Brookfield Park			S	P	Add a walking trail through the park.			L/F
VI.f.4		Galloway Park			S	P	Add a walking trail through the park.			L/F
VI.f.5		Greenway Arboretum			S	P	Improve on walking trails; obtain public access.			L/F
VI.f.6		S. Main St. park land			S	P	Add walking trails, recently donated park land			L/F
VI.h.1		Main St.	Merrill	Western	C	P	Stencil "walk your bike" onto downtown walk			I/M
VI.h.2		Downtown	various		B	P	Install larger bike racks at downtown entrances.			I/M
VI.j.1		Parks	various		B	P	Install bike racks in various City parks			I/M
VII.b.1		Various			C	C	Add trail/mileage signs around system.			I/M
VII.c.1		Various			C	C	Add information kiosks at trailheads of State trails			I/M
VII.d.1		Various			C	C	Develop maps, place at businesses, kiosks, web			I/M
VII.e.1		Festival Foods	parking lot	Prairie Tr.	C	C	Add signage to direct bikers/joggers from Festival parking lot to trail; acts as Park & Ride			I/M
VII.g.1		Various			C	C	Add regulatory/warning signage to bike trails. Especially inconsistent on Brooke and River trails now.			I/M, I/S
VII.h.1		Martin Ave.	Willsher	Park Ave.	C	C	Improve signage to connect Pioneer & Prairie trails			I/M
VII.h.2		Hampton/Willsher	Hwy V	Martin	C	C	Improve signage on this part of the in-town marked routes.			
VII.i.1		Various			C	C	Work w/ DFP, CVB to coordinate wayfinding signs specifically for bicyclists and pedestrians.			I/M
VII.j.1		Various			C	C	Install destination signs to direct people to parks, attractions, school, arboretums, etc.			I/M
VII.k.1		Various			C	C	Sign "alternative loops" uniquely (Park Ave., Harbor View, Hwy WH, etc.).			I/M
VII.m.1		Prairie Tr.	various		C	C	Stripe centerline or install warning signs at blind corners of Prairie Trail			I/M

[1] Project Category: S = sidewalk only, B = on-street bike accommodations only, M = multi-purpose trail, C = Communication (signs, markings) only.

[2] Plan Section: L = bike loop, State = Links to State trails, DOT =part of State/County project, B = local bike need, S = local sidewalk need, P = policies, C = Communication (signs, markings) only.

[3] Estimated Cost: Unless otherwise noted, cost estimates are based on in.gov survey dated March 2011.

[4] Urgency/Opportunity: **I/S** = immediate need for safety reasons, **I/F** = immediate opportunity as funding is available, **I/M** = immediate opportunity as the project is minor, **L/F** = long-term goal with funding challenges, **L/E** = long-term goal with engineering challenges, **L/P** = long-term goal as this should be tied to a larger project.